

113 Ennis St, Unit A Saraland, AL 36571 251-725-0130

QUOTE # 53860 / UTLI46A Forestry Unit / 50ft Working Height

NOTE: All pricing subject to change based on Tariff and/or significant price fulctuations

Part Number	Qty	Product Description
UTLI46A	1	UTEM UTLI46A Insulated, Full Pressure, Articulated/Telescopic Aerial Device
701066	1	Truck Mount Pedestal, 42"T
701160	1	Pedestal Riser 16"
	1	Reverse Mount Turret
		Fiberglass Upper Boom W/ Reverse Mount Knuckle (Upper Boom Towards
	1	Streetside)
		Reverse Mount Lower Boom W/ Chassis Isolation System (Provides 12" Lower
	1	Boom Insulation Gap)
702662	1	Hydraulic Rotator for Top Mount Platforms
701120	1	Single Stick Control with End Mount Platform
703212	1	HM Hydraulics For 12V System - Chevy/GM
701060	1	Manual 6-Spool Control Valve
701068	1	540 Degree Non-Continuous Rotation
700867	1	Chassis Pedestal Mount
700535	1	350lb. (159kg) Platform Capacity
501070	1	24x24x42 Fiberglass Basket W/ Center Walk Thru & Door
426551	1	Soft Vinyl Basket Cover (Fits 24x24 Basket)
701054	1	Emergency Lowering with "HM" Hydraulics
701151	1	Hydraulic Tool Circuit with Single Stick Controls for End Mount
701057	1	Manual Two-Speed Throttle (Signal Only)
500600	1	UTEM White Powder Coat
613190	1	Dielectric Cert- Cat C 46kV and Below (Req Boom Tip Covers)
702850	1	Boom Tip Covers For Top Mounted Hydraulic Rotator
703572	1	HD H-Frame Outriggers 5"x5"x97" With Outrigger Boom Interlock

ALL PRICES F.O.B. HEWITT, TEXAS

Arbortech Steel Chipper Box

90"L x 96"W x 54"T

Curbside Interior Ladder Box With Pruner Shelf & Locking Rear Door 24"T Swing To Side Tailgate

Upper Panel Vents

5"T Long Sills

Coal Tar Interior Of Chip Box

Undercoated Underside Of Chip Box

LED Light Package W/ 6 & 7 RV Style Trailer Plug

4-Head Amber Strobe

Boom Rest

Wheel Chock Holders & Wheel Chocks Provided

Metro Deck Wrap Around Box

Painted White

Subframe Hoist Intalled To Longsills Of Box

Electric Pump For Subframe Hoist

15,000# Tow Package (Includes Pintle Hook)



^{*}Two complete sets of manuals and one safety harness and lanyard are provided with each unit.

^{*}Quote Good For 30 Days

^{*}Aerial Compliant W/ ANSI Standard A92.2-2015

Installation

Install Hydraulic Outriggers Behind Cab On Chassis Frame
Install Aerial Mounting Hardware On Chassis Frame
Install Metro Deck Wrap Around Box
Fabricate & Install Full Cab Guard
Install Access Ladder
Install Hoist On Chassis Frame
Install ArborTech Chipper Box
Wire DOT Body Lights

Install PTO & Pump For Chevy 5500 Install UTEM Aerial Model# UTLI46A Reverse Mount

Wire PTO For Start/Stop

Install Hydraulic Hoses, Fittings, Components & Oil

(Qty 2) Amber LED Beacons

(Qty 4) 5" LED Amber Strobes (2 Mounted @ Rear/ 2 Mounted On Front Bumper)

(Qty 2) Mud Flaps Installed

(Qty 2) Wheel Chocks Provided

Fire Extinguisher, 5# Provided

Non Skid Deck

Install Chevy Factory Back UP Camera

Back Up Alarm Installed

DOT Reflector Kit

Quick Disconnect Kit

Fabricate ICC Bumper

Paint Deck, Access Ladder & Cab Guard White

Includes Labor To Install

LEAD TIME IS OCTOBER 1ST, 2025 DELIVERY IF ORDERED TODAY



Total: \$213,000.00 + Tax & Delivery

Chassis

2025 International CV515 SFA 4x4 Conventional Cab

165"WB / 84"CA
International 6.6 350HP Diesel Engine
Allison 2750 RDS 6th Generation 6-Speed Auto Transmssion (Double Overdrive)
23,500# GVWR
Keyless Entry Remote
PTO Provisions